

Bid No. 13-29
Town of Groton, Connecticut 06340

Vinyl Composition Flooring

4/23/2013
2:30 PM

	BT Tile + Carpet	Mazzella Carpet
Total cost for vinyl composition flooring at Water Pollution Control Facility	1,975.00	1,098.64
Time to complete project in weeks after receipt of award	2 weeks for material -- 3 days to complete project	1 - 2 weeks
	Bid Substitution:	Note: Price based on Azrock Standard Color Patterns; 73 colors available @ Standard Pricing.
	BT Tile and Carpet would like to substitute the self leveling material from Ardex K-15 to Ardex LU-100.	Note: Sqft total includes Overage; Available by box only @ 45sqft/Box
	The K-15 requires a mechanical cleaning (Bead blast-scarify) of the surface to provide a surface to bond to. The mechanical cleaning was not included in the specifications provided but is needed to be done with this product.	Note: Floor heights and material being reduced to need to be verified
	The LU-100 is designed to go over products that are smooth or have residue on them that is structurally sound. See bid for specs.	Note: Bid price based on assumption that all existing quarry tile is set properly, free of cracking, and firmly in place to accept Self Leveling underlayment and VCT Flooring; Repair of loose or broken Tiles not included in this bid.
	BT has spoken with an Ardex rep and the rep agrees with recommendation.	