TOWN OF GROTON

PUBLIC WORKS DEPARTMENT

GARY J. SCHNEIDER
DIRECTOR
PWORKS@GROTON-CT.GOV

134 GROTON LONG POINT ROAD, GROTON, CONNECTICUT 06340
TELEPHONE (860) 448-4083 FAX (860) 448-4094
WWW.GROTON-CT.GOV

PROJECT: Noank Town Dock Pier Reconstruction and Seawall Maintenance

ADDENDUM # 2

DATE: October 6, 2016

TO: Invited prime bidders and others who have secured bid documents from the Owner.

ACKNOWLEDGE receipt of this addendum by inserting its' number and date in the proposal form. Failure to do so may subject bidders to disqualification. This addendum forms a part of the Bid Documents.

It modifies them as follows:

ADD:

1. **To clarify the plans; the new 1 ½" galvanized steel rail is to be installed on <u>both</u> sides of the steps leading to the beach.**

2. **Include Alternate Bid No. 3 to substitute the 1 ½" galvanized steel rails (base bid) with 1 ½" stainless steel rails.**

3. **Replace the bid schedule with the attached revised schedule.**

4. **To clarify the plans, the entire sea wall (approximately 120') is to be repointed.**

5. **Delete Section 02362, Paragraph 2.03 in its entirety and substitute the following:**

    - **2.03 DECKING: Decking shall be Southern Yellow Pine, grade 1, treated with ACQ to 0.60 lbs/cf. Size is nominal 3x8.**

- End of Addendum # 2 –

NOANK TOWN DOCK PIER RECONSTRUCTION
AND SEAWALL MAINTENANCE
GROTON, CONNECTICUT

TOTAL

THE TOTAL LUMP SUM BASE BID FOR ALL WORK INDENTIFIED AS BASE BID OR NOT OTHERWISE IDENTIFIED AS AN ALTERNATE BID ITEM, COMPLETED AND IN PLACE, AS COMPUTED BY THE BIDDER:

IN FIGURES: _____

IN WORDS: _____

UNIT PRICE ALTERNATE BID NO. 1: FOR FENDER PILES COMPLETE AND IN PLACE, PER EACH

IN FIGURES: _____

IN WORDS: _____

UNIT PRICE ALTERNATE BID NO. 2 FOR TAYLOR MADE FENDERING ON ALL PIER PERIMETER PILES COMPLETE AND INPLACE, PER EACH:

IN FIGURES: _____

IN WORDS: _____

LUMP SUM ALTERNATE BID NO. 3 FROM STAINLESS STEEL PIPE RAIL IN LIEU OF GALVANIZED STEEL COMPLETE AND IN PLACE, PER LUMP SUM:

IN FIGURES: _____

IN WORDS: _____